BRUHATH BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of Work: Estimate for Providing Covering Slab to Existing Drains at Bloom Field Garden in Ward No. 10, Doddabommasandra, Vidyaranyapura Sub Division.

					Estimate Cost:			1500000.00	
Sl No.	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 **Page No. 152 / Item No. 19.2 / PWD SR 2013-14**	Cum							
	Desilting of Drains		2	90.00	0.50	0.35	31.50		
			2	95.00	0.50	0.35	33.25		
			2	85.00	0.50	0.35	29.75		
	Berm Cutting		2	90.00	0.90	0.20	32.40		
			2	95.00	0.90	0.25	42.75		
			2	85.00	0.90	0.25	38.25		
							207.90	90.72	**18861.00**
	Basic Rate	84.00							
	Area Weightage @ 8%	6.72							
	Total	**90.72**							
2	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. **Page No. 19 / Item No. 4.48.1/ PWD SR 2013-14**	Cum							
	Went Concrete		2	75.00	0.45	0.10	6.75		
			2	95.00	0.45	0.10	8.55		
			2	60.00	0.45	0.10	5.40		
	Side Walls Damaged portion		2x2	75.00	0.15	0.30	13.50		
			2x2	95.00	0.15	0.45	25.65		
			2x2	60.00	0.15	0.45	16.20		
	For Road Sides		2	90.00	0.45	0.15	12.15		
			2	95.00	0.45	0.15	12.83		

Sl No.	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
			2	85.00	0.45	0.15	11.48		
							112.50	6464.88	**727299.00**
	Basic Rate	5986.00							
	Area Weightage @ 8%	478.88							
	Total	**6464.88**							
3	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 10 cms thick **Page No. 28 / Item No. 5.31.2 / PWD SR 2013-14**	Sqm							
			2	90.00		0.75	135.00		
			2	95.00		0.75	142.50		
			2	85.00		0.75	127.50		
				270.00			**405.00**	579.96	**234884.00**
	Basic Rate	537.00							
	Area Weightage @ 8%	42.96							
	Total	**579.96**							
4	KSRB 5-9: Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 **Page No. 27 / Item No. 5.22/ PWD SR 2013-14**	m							
			1200	2.40			**2880.00**	28.40	**81804.00**
	Basic Rate	26.30							
	Area Weightage @ 8%	2.10							
	Total	**28.40**							
5	KSRB 5-8.2 : Providing two line dressing to granite stone slab / granite stone masonry as per specifications. KBS 5-1.13 **Page No. 26 / Item No. 5.18/ PWD SR 2012-13**	Sqm							
			2	90.00		0.75	135.00		
			2	95.00		0.75	142.50		
			2	85.00		0.75	127.50		
							405.00	653.40	**264627.00**
	Basic Rate	605.00							
	Area Weightage @ 8%	48.40							
	Total	**653.40**							

Sl No.	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
6	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum					155.93		11337.00
			Qty Vide Item No. 1				278.65	72.71	20259.00
	Basic rate for haulage of materials as per item no.17.4 page 118) Rs. 2.00								
	Average weight of earth 1.28 tonne / kg for 2x1.28x2.00=5.12	5.12							
	Add loading and unloading Vide item no.17.1 P.no.118	62.20							
		67.32							
	Area Weightage @ 8%	5.39							
	Total	**72.71**							
7	Sub Total								1339200.00
8	KRIDL Charges @ 11%								147312.00
9	QC Charges @ 1%								13392.00
10	Miscellaneous and unforeseen charges	LS							96.00
								Total	1500000.00

(Rupees Fifteen Lakhs Only)

Technical Sanction for Rs. Fifteen Lakhs only
Registered as E&T No. 336/13-14, 03/03/2014 Dated Subject to conditions contained enclosed memo. No: 336/13-14 03/03/14 Dt.
AEE/JE
EE (BTP.Div.)

CERTIFICATE:

1. Certified that I have personally inspected the area and prepared the Estimate.
2. Certified that the above estimate is prepared as per PWD SR 2013-14.
3. Certified that the work proposed in this estimate is not including in any other scheme.
4. The provisions were made in this estimate are necessary and adequate.
5. This works come under B.B.M.P. limits.

Assistant Engineer

Assistant Executive Engineer
Vidyaranyapura Sub Division
B.B.M.P., Bangalore.

Executive Engineer
Byatarayanapura Division.
B.B.M.P., Bangalore.

ADMINISTRATIVELY SANCTIONED FOR Rs. 15.00 Lakhs
Rupees Fifteen lakhs Only
Under P-0190
Registered as E&T No. 3.....9.....
Subject to conditions contained in enclosed memo No. .....191.....
Dt .....
Sanctioned
Addl Comr(Yz) AS/920/13-14
dated 26/2/2014 Rs 15.00 lakhs

Addl Commissioner
(Yelahanka Zone)
BBMP, Bengaluru-92